6000 SERIES Standard-Duty

- Constructed of 11/2" x 11/2" square tubing with a .070" thick wall.
- All seams are completely welded and sealed from dirt and debris.
- Legs are sealed with a plastic cap.

One Year Guarantee against material defects and workmanship.



Mobile Dunnage Rack with Upgrades!

- Constructed of 11/2" x 13/4" tubing with a .070" thick wall.
- All seams are completely welded and sealed from dirt and debris.
- Upgraded with a custom tow loop to be used with our 1199 Drag Hook.
- Outfitted with a removable handle, Model # 1208, and 5" plate type casters; two rigid, and two swivel with a brake.

DUNNAGE RACK Comparison Chart

All **New Age** equipment is built from primary-grade aluminum billets, extruded on site at our facility in Norton, Kansas.

2000 SERIES

Heavy Duty Series

- Constructed of $1\frac{1}{2}$ " x $1\frac{3}{4}$ " tubing with a .070" thick wall.
- All seams are completely welded and sealed from dirt and debris.
- Legs are sealed shut with an .125" thick aluminum cap.

Five Year Guarantee against material defects and workmanship!

